BHADRAVATI DIVISION.

Abstract Notification.

The attention of the public is invited to the notification dated 20th January 1925, published in pages 94 and 95, Part VI of the *Mysore Gazette* for week ending 29th January 1925 calling for tenders for the collection and removal of bamboos in the several forests of this Division.

M. MACHAIYA,
District Forest Officer.

ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Notification dated 6th February 1925.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division up to the 28th February 1925, for opening out a feeder channel to Malur-Doddakere Register No. 41 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1925.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees one hundred and fifty only (Rs. 150) in cash or Government promissory notes, as earnest money and be superscribed "Tender for opening out a feeder channel to Malur Doddakere Register No. 41 of Malur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. In matter of all disputes about rates, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Chief Engineer will be final and legally binding.

Statement showing the appropriate estimate of quantities of work to be done for opening out a feeder channel to Malur Doddakere.

Serial No. of items	Items of work	Unit	Quantity
1	Excavating earthwork mixed with hard gravel and forming bank ..	C.yd.	9,202
2	Concrete in mortar	C.ft.	119
3	Burnt brick in surki mortar	,,	559
4	Burnt stone slabs dressed 6" thick	S.ft.	100
5	Plastering with surki mortar	Sqr.	7 00
6	Rough or burnt stone new	C.yd.	83
7	Rough stone Irish drain for passing cart	,,	Lumpsum
8	Do do for cattle	,,	Do
9	Protecting sides at C. S. No. 11	,,	Do
10	Grade stones	No.	11
11	Furlong stones	,,	6
12	Constructing silt dam with rough stone	,,	Lumpsum

C. T. NARASIMHA IYENGAR,
Executive Engineer.
6 c